BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK : Providing basic amenities,Procurement of dustbins and SWD works in ward No.13,Mallasandra.

Sl No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	6.84	211.79	Rupees Two Hundred Eleven And Paise Seventy Nine Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	1.03	5505.64	Rupees Five Thousand Five Hundred Five And Paise Sixty Four Only
3	Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	6.84	213.06	Rupees Two Hundred Thirteen And Paise Six Only
4	4.0 Mega Pixel high definition upto 60Mtr IR Night Vision CCTV Camera-EXIR with SD Card Provision (Data Rate Approved)	No's	57.00	16247.00	Rupees Sixteen Thousand Two Hundred Forty Seven Only
5	Supplying Pole for PTZ Erection woth Civil Work Engineer in Charge of work (Data Rate Approved)	Each	19.00	17175.00	Rupees Seventeen Thousand One Hundred Seventy Five Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Signature Of The Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
6	Supplying Of 6U Rack with SS Lock & Key (Data Ra/te Approved)	No's	19.00	5400.00	Rupees Five Thousand Four Hundred Only
7	Junction Metal Box (Data Rate Approved)	No's	19.00	450.00	Rupees Four Hundred Fifty Only
8	5 Port Switch (Data Rate Approved)	No's	19.00	575.00	Rupees Five Hundred Seventy Five Only
9	HDMI Splitter or Auto Video Switch Output (Data Rate Approved)	No's	19.00	2905.00	Rupees Two Thousand Nine Hundred Five Only
10	Power Adopter (Data Rate Approved)	No's	19.00	290.00	Rupees Two Hundred Ninety Only
11	Supply and Installation/Fixing/Provision of Outdoor type Thermoplastic Modular Panel Enclosure with Transparent Polycarbonate Lid Shock Proof IP65 (weather Proof) Rust proof Dust Proof, water proof Corrosion proof having internally embedded gasket on both lid and flap suitable to fix singale phase/ Three Phase Energy Meter in suitable base plate and having a provision for fuse/MCB Cutout along with complete tamper proof SEALING facility 600mm X 600mm X 170MM	Each	2.00	13728.00	Rupees Thirteen Thousand Seven Hundred Twenty Eight Only
12	UPS 2Hours Backup	No's	46.00	8704.00	Rupees Eight Thousand Seven Hundred Four Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
13	Battery 2 Hours Backup	No's	1.00	10776.00	Rupees Ten Thousand Seven Hundred Seventy Six Only
14	Supplying of 32 Channel NVR (NVR defulat without HDD) with 2SATA H264 Compression Engineer in Charge of work (Data Rate Approved)	No's	2.00	38000.00	Rupees Thirty Eight Thousand Only
15	Supplying of 4 TB Harddisk-seagate Engineer in Charge of work (Data Rate Approved)	No's	8.00	13000.00	Rupees Thirteen Thousand Only
16	Supplying of 4+4 POE switch TP link Engineer in Charge of work (Date Rate Approved)	No's	19.00	7174.00	Rupees Seven Thousand One Hundred Seventy Four Only
17	Suuplying of 4 Pin Spike Pin Cana/reputed Engineer in Charge of work (Date Rate Approved)	Each	38.00	1145.00	Rupees One Thousand One Hundred Forty Five Only
18	Outdoor Supportable CAD6/CAD5 Cable /Power Cable FRLS (Data Rate Approved)	Permtr	3040.00	140.00	Rupees One Hundred Forty Only
19	Outdoor Supportable CAD6/CAD5 Cable /Power Cable Cabling,Laying Charges	Permtr	3040.00	140.00	Rupees One Hundred Forty Only
20	HDMI Patch cable for connectivity Engineer in Charge of work (Data Rate Approved)	No's	57.00	550.00	Rupees Five Hundred Fifty Only
21	Supplying Of 12V/2.5A Adopter (Data Rate Approved)	No's	57.00	285.00	Rupees Two Hundred Eighty Five Only

Signature Of The Contractor

EXECUTIVE ENGINEER-1
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
22	Circuit Breaker For CC TV Protection (Data Rate Approved)	No's	57.00	252.00	Rupees Two Hundred Fifty Two Only
23	Supplying of Hardware items and fixing charges Engineer in Charge of work (Data Rate Approved)	Each	57.00	1450.00	Rupees One Thousand Four Hundred Fifty Only
24	CPU - i3 Processer- 450 MHZ, 8Gb Ram, 250Gb Hard Disk Full Core (Date Rate Approved)	No's	2.00	41564.00	Rupees Forty One Thousand Five Hundred Sixty Four Only
25	Installation Charges for Camera and NVR Engineer in Charge of work (Date Rate Approved)	Set	59.00	4050.00	Rupees Four Thousand Fifty Only
26	IP Configuration Engineer in Charge of work (Date Rate Approved)	Each	59.00	3230.00	Rupees Three Thousand Two Hundred Thirty Only
27	Supplying Of 42" LED TV Make Samsung/LG/Philips/Videocon (Date Rate Approved)	Each	2.00	70952.00	Rupees Seventy Thousand Nine Hundred Fifty Two Only
28	1 Year Maintainance Checking of NVR Quaterly Check	Each	1.00	150480.00	Rupees One Lakh(s) Fifty Thousand Four Hundred Eighty Only
29	Dustbin 2 No's with bag top width-285mm, Height-250mm, Bottom width-190mm, Material-Reprocesed poly propoylene, Colour-Blue,Green,Red.weight 280-300gm (Approved Quotation Rates enclosed)	No/Set	2480.00	100.00	Rupees One Hundred Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner